(*i*) Neither the lessee nor his employees shall enter the forest either before sunrise or after sunset.

(*j*) The lessee shall deposit Rs. 100 (one hundred only) as security for the due fulfilment of the conditions of the lease. In the event of the breach of any of the above conditions, the money deposited as security shall be forfeited to Government in whole or in part as the Conservator of Forests may decide and the lease liable to be cancelled.

5. No bamboos should be collected between 15th February and 30th April in the State Forest.

6. The sale does not prohibit the issue of retail licenses at seigniorage rates or the exercise of the rights of the villagers.

7. The highest bidder shall, at the close of the sale, also credit into the Treasury Local cess at one anna per rupee, Railway cess at three pies per rupee, and Education cess at six pies per rupee on the entire sale amount. In default, the deposit will be forfeited and the right resold subject to the conditions stipulated in para 2.

— —

Notification dated 16th December 1924.

It is hereby notified for the information of the public, that one green teak pole measuring twelve feet in length and five feet in girth, found near Survey No. 54/2, of Tyagaravally village, Kunsi Sub-Taluk, is kept in the custody of Patel Nandibasappa, Tyagaravally village.

The claimants if any are required to present and establish their claims before the District Forest Officer, Shimoga Division, within one month from the date of publication of this notice, failing which, the said log will, under Sections 40 and 42 of the Mysore Forest Regulations, be confiscated to Government.

L. P. MASCARENHAS,
District Forest Officer

SAGAR FOREST DIVISION.

Abstract Notification dated 13th December 1924.

The attention of the public is invited to the detailed Notification regarding the auction sale of Inam in the following Depots of this Division on the dates noted against each published on pages 996 and 997, Part VI of the *Mysore Gazette*, dated the 18th December 1924.

Name of Depot	Date of sale
Sagar	17th January 1925 Saturday.
Ananthapur	19th January 1925 Monday.
Chordi	20th January 1925 Tuesday.
Sowlinga	21st January 1925 Wednesday.
Shikarpur	23rd January 1925 Friday.
Shiralkoppa	26th January 1925 Monday.
Anawatti	28th January 1925 Wednesday.
Shakunavalli	30th January 1925 Friday.

K. REVANNA,
District Forest Officer.

ENGINEERING DEPARTMENT.

SPECIAL WATER SUPPLY CONSTRUCTION DIVISION.

Notice dated 19th December 1924.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Special Water Supply Construction Division, Bangalore, up to 12 noon of 3rd February 1925, for the construction of Filter Beds, Service Reservoir, Settling Tanks, Watchman's Shed, and Temporary Office Shed for Water Supply to the Tumkur Town. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1926.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, on all working days between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 2,000 in cash or Government promissory notes, as earnest money and be superscribed "Tender for the construction of Filter Beds, Service Reservoir, Settling Tanks, Watchman's Shed and Temporary Office Shed for Water Supply to Tumkur Town," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Government who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of any tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne entirely by the contractor.

10. In all matters not specially provided for, and in all matters of disputes about rates, quantities, measurements, and quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer of Mysore will be final and legally binding.

11. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

Abstract of quantities of work to be done for the construction of "Settling Tanks, Filter Beds, Service Reservoir, Watchman's Shed and Temporary Office Shed" in connection with the Tumkur Water Supply Project.

Serial No.	Detail of work	Unit	Quantity
	SETTLING TANK.		
1	Earth work excavation in gravelly soil	C. yd.	3,498
2	Do in soft rock	,,	427
3	Do refilling, and tamping for pipe line in gravelly soil ..	,,	341
4	Stone concrete in surki mortar 1 : 2	C. ft.	9,032
5	Burnt brick in surki mortar	,,	5,102
6	Do on edge in surki mortar	,,	6,495
7	Burnt stone slabs 4½" to 6" thick two line dressed and set in mortar	S. ft.	372
8	Plastering with surki mortar 1 : 1 : 1 including rounding of all corners	Sqr.	249·51
9	Forming spoil bank with excavated earth	C. yd.	3,498
10	Turfing sides of spoil bank	Sqr.	227·5
11	Drilling holes in slab and fixing valve shutters 2½' x 2½' with bolts, nuts, etc., complete.	No.	6
12	Laying and jointing with lead 9" C. I. pipes including cuts, fixing specials valves, etc., complete.	Joint	24
13	Laying and jointing with lead 4" C. I. pipes	,,	33
14	Flange joints on 9" pipes and valves excluding bolts, nuts and washers	,,	8
15	Do 4" pipes	,,	4
	FILTER BEDS.		
1	Earthwork excavation in gravelly soil	C. yd.	2,484
2	Do in soft rock	,,	310
3	Do refilling and tamping for pipe line in gravelly soil ..	,,	318
4	Stone concrete in surki mortar 1 : 2	C.ft	14,155
5	Burnt brick in surki mortar	,,	15,013
6	Burnt stone slabs 4½" to 6" thick two line dressed and set in mortar	S ft.	678
7	Burnt stone slabs 3" to 4" thick two line dressed and set in mortar with one edge champhered	,,	676
8	Plastering with surki mortar 1 : 1 : 1 including rounding of corners	Sqr.	153·87
9	Forming spoil bank with excavated earth	C. yd.	2,352
10	Turfing sides of spoil bank	Sqrs.	152.88
11	One and a half inch Cuddapah slabs for covering drains including laying ..	,,	15·12
12	Forming surki concrete semi-circular drain 1' diameter, including plastering ..	R. ft.	144
13	Do do do 9" drains	,,	402
14	Scooping out 3" drains in concrete bed including plastering	,,	600
15	Covering drains with burnt bricks laid dry	Per 1,000	272
16	Collecting, carting through a distance of 3 to 4 miles and charging filtering materials after proper sieving and washing as per specification.	C yd.	..
	(a) Jelly 1½" to 1"	,,	244
	(b) Do 1" to ½"	,,	122
	(c) Pebbles ½" to ¼"	,,	122
	(d) Coarse sand passing through a sieve with 10 meshes per lineal inch and retained on one with 20 meshes	,,	122
	(e) Fine sand passing through a sieve with 20 meshes per lineal inch and retained on one with 40 meshes.	,,	611
17	Nine inch Cornice work in mortar	R. ft.	141
18	Drilling holes in slab and fixing valve shutters 2½' x 2½' with bolts nuts, etc., complete	No.	15
19	Fixing "V" Notches in masonry	,,	3
20	Writing gauges 3' high on the walls of the filters and painting them	,,	6
21	Providing and fixing rain water spouts 3" in diameter add 2' in length	,,	6
22	Laying and jointing with lead 9" C. I. pipes including cuts, fixing specials valves, etc., complete.	Joint	45
23	Laying and jointing with lead 4" C. I. pipes	,,	55
24	Do do 2½" C. I. pipes	,,	15

Serial No.	Detail of work	Unit	Quantity
25	Flange joints on 9" pipes and valves excluding bolts, nuts and washers ..	Joints	12
26	Do 4" pipes do	,,	6
27	Do 2½" pipes do	,,	12
	SERVICE RESERVOIR.		
1	Earthwork excavation in gravelly soil	C. yd.	2,115
2	Do in soft rock	,,	264
3	Do refilling and tamping for pipe line in gravelly soil ..	,,	261
4	Stone concrete in surki mortar 1 : 2	C. ft.	9,960
5	Burnt brick in surki mortar	,,	17,000
6	Do in surki mortar for arch work	,,	1,132
7	Burnt stone slabs 4½" to 6" thick two line dressed and set in mortar	Sq. ft.	352
8	Plastering with surki mortar 1 : 1 : 1 including rounding of corners	Sqr.	207·94
9	Forming spoil bank with excavated earth	C. yd.	2,115
10	Turfing sides of spoil bank	Sqr.	139·41
11	9" cornice work in mortar	R. ft.	300
12	6" cornice work in mortar	,,	440
13	Lifting and fixing rolled steel joists 6" x 3" 17' to 25' in length with fish plates, bolts and nuts after drilling holes. Only the rolled steel joists will be supplied by the Department.	No.	56
14	Jack arch, terrace work with two courses of flat tiles and 3" concrete on crown, plastering, etc., complete.	Sqr.	53·3
15	White wash in two coats	,,	30·00
16	Colour wash do	,,	30·00
17	Supplying and fixing iron ladders 14' in height with sides of flat iron and rungs of roundbars 1' apart, the top and bottom ends being bent to be fixed in masonry.	No.	2
18	Do iron ladders 6' in height do	,,	1
19	Supplying and fixing ventilators 2' x 1' with expanded metal of ½" mesh set in flat iron frames.	,,	40
20	Forming drain 12" x 9" with burnt stone slabs at the bottom and size stones in surki for sides.	R. ft.	1,200
21	Writing gauges 10' high on the walls and painting them	No.	2
22	Providing and fixing a date stone 1½' x 1' polished and the date cut on it ..	,,	1
23	Supplying and fixing rain water spouts 3" in diameter and 3' in length ..	,,	8
24	Do an iron wicket gate 2½' x 2' in the parapet wall	,,	1
25	Drilling holes in slab and fixing valve shutters 2½' x 2½' with bolts, nuts, etc., complete.	,,	4
26	Fixing valve shutters 2½' x 2½' with bolts and nuts in the roofing	,,	2
27	Laying and jointing with lead 9" C. I. pipes including cuts, fixing specials, valves, etc , complete.	Joint	23
28	Do 4" C. I. pipes	,,	20
29	Flange joints on 9" pipes and valves excluding bolts, nuts and washers ..	,,	8
30	Do 4" pipes do ..	,,	4
	WATCHMAN'S SHED.		
1	Earthwork excavation in gravelly soil	C. yd.	15
2	Burnt stone in chunam mortar	C. ft.	540
3	Burnt brick in chunam mortar	,,	138
4	Do in mud	,,	871
5	Burnt stone slabs 4½" to 6" thick two line dressed and set in mortar	Sq. ft.	111
6	Plastering with chunam mortar	Sqr.	15·79
7	White wash in two coats	,,	15 79
8	Colour wash in two coats	,,	15·79
9	Teakwood wrought and put up including wood oiling	C ft.	36·42
10	Roofing with first class Mangalore tiles on teak reepers	Sqr.	6·73
11	Ridge tiles set in mortar	R. ft.	26
12	Flooring with cuddapah slabs 1" thick on 3" of brick in chunam concrete ..	Sqr.	2·53
13	Teakwood battened doors complete with hook, hinges, etc,.	Sq. ft.	36
14	Teakwood windows with iron bars, half glazed and half battened	,,	24
15	T. W. plane eave board 9" wide	R. ft.	104
16	Chaculate painting in two coats	Sqr.	2·76
17	Earthwork refilling and tamping	C. yd.	15
18	Providing almirahs in walls with teakwood shutters	Sq. ft.	12
	TEMPORARY OFFICE SHED.		
1	Earthwork excavation in gravelly soil	C. yd.	1
2	Burnt brick in mud	C. ft.	46
3	Jungle wood poles 4" in diameter put up	R ft.	273
4	Thatty walls filled with clay, plastered with chunam and white washed ..	Sqr.	5 30
5	Jungle wood door with battened shutters	Sq. ft.	18
6	Bamboo rafters 3" to 4" in diameter put up	R. ft.	200
7	Roofing with mats and hay on areca reepers	Sqr.	4·60
8	Filling earth, tamping ground and flooring with chunam mortar on 3" concrete ..	,,	2·40

Notification dated 5th December 1924.

It is hereby notified for the information of the public that stores enumerated in the statement hereunder will be sold by public auction on 10th January 1925 at Bangalore at the premises of Special Water Supply Construction Division.

2. The materials selected for the sale will be available at the site for examination on the previous day with the permission of the Assistant Engineer who will be at the spot.

3. The terms and conditions of the sale are:—

(*a*) that the article or articles will beknocked down to the highest bidder and that in the event of any dispute arising between two or more bidders at the same price. the article or articles will be put up again and resold;

(*b*) that all the articles purchased shall be at the risk of the purchaser thereof from the time of the sale;

(*c*) that all articles should be removed with faults and errors of all description as sold;

(*d*) that cash should be paid in full for article or articles purchased by bidders before delivery, but that the articles will not be allowed to be removed from the place of auction until after close of sale;

(*e*) that in case of default of the payment of the whole or any portion of the purchase amount due by any bidder, the articles will be resold and the bidder will be liable to any loss incurred thereby;

(*f*) that a deposit of 10 per cent of the amount will be made by the successful bidder immediately the articles are knocked down in his favour, and that such deposits shall be treated as forfeited to Government in case of any default to pay the purchase money within the time prescribed in clause (*g*). Also that on resale as laid down in clause (*e*), the bidder will be liable to make good any loss incurred thereby, without having the right to participate in any excess realised;

(*g*) that the purchase money should be paid up within three days from the date of sale and that the articles purchased should be removed immediately thereafter;

(*h*) that the sale shall be subject to confirmation by the Executive Engineer.

LIST OF AUCTION SALE OF STORES.

Sl. No.	Description of articles	Unit	Quantity
1	2½" Cast Iron Pipes	No.	3
2	7" Stoneware pipes	No.	14
3	Drain cleaning rods	No.	1
4	Lead pipes	R.ft.	2½
5	4" Wrought Iron pipe 10' long	No.	1
6	½ Ball valve	No.	3
7	2½" Lead trap	No.	2
8	4" Cast Iron pipe	R.ft.	12
9	2½" Cast Iron pipe	R.ft.	25
10	1¼" Galvanised Iron Flush pipe for 3 gallon cistern ...	No.	1
11	Copper ball valves for Cast Iron Cistern	No.	2
12	Old flush pipe that were partly eaten away by soil rust ...	No.	2

H. F. MARKER,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 1st December 1924.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, Tumkur, up to 12 noon on 5th January 1925, for restoring the Mavinkere Minor Tank, Registered No. 150 of Turuvekere Sub-Taluk.

Each tender must be accompanied by a deposit of Rs. 200 (two hundred only) in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring the Mavinkere Minor Tank, Registered No. 150 of Turuvekere Sub-Taluk," in default of which it will be rejected.

Tenders should be submitted in the printed forms, which are available in the Executive Engineer's Office. No tender form, not initialed by the undersigned, will be accepted.

V. V. KARVE,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

FRENCH ROCKS SUB-DIVISION.

Notification.

In place of words "8th December 1924" printed in line 7 of notification dated 16th November 1924 published in page 936, Part VI of the *Mysore Gazette* dated 27th November 1924, please read as "24th December 1924."

K. SUBBA RAO,
Sub-Division Officer,
French Rocks.